



5580 Enterprise Pkwy., Fort Myers, FL 33905  
Office: (239) 694-0089 Fax: (239) 694-0031

*Total Solution for all your Control Needs*

## North Fort Myers High School

Fort Myers, Florida



**\$7000.00 DOLLARS SAVED BY  
THE SCHOOL DISTRICT !**

**NEW COMPRESSOR WITH TWO YEAR WARRANTY !**



*Total Solution for all your Control Needs*

## North Fort Myers High School

### Site Location:

- North Fort Myers High School  
North Fort Myers, Florida  
Lee County School District

### Concerns:

- Cost of Trane rebuilt compressor
- How would Hanbell fit in RTAA frame
- How would oil return be guaranteed to the Hanbell compressor
- How would the Trane controller respond to the Hanbell compressor

### Equipment:

- One Trane RTAA 400 ton Chiller
- Two (2) Refrigerant Circuits
- Two (2) Compressors per Circuit
- Two (2) EXV's per Circuit
- Air Cooled Condenser
- Two (2) U-Tube Oil Separators per Circuit
- One (1) Oil Pressure Differential Switch per Compressor

### Steps Taken:

- Removal of Trane CHB100 Compressor
- Install 3/8" steel plate to RTAA frame
- Install MCS Hanbell RC15LF Compressor (changed load solenoid to normally closed)
- Utilize existing Trane controls

### Results:

Compressor #2 on circuit #1 had failed. The Trane compressor was removed and a 3/8" steel plate was installed and bolted through the original Trane compressor mounting holes. The Hanbell compressor was positioned on the plate to allow for the best piping connections. Mounting holes were then made in the plate for the Hanbell compressor. Once the Hanbell was bolted into place, the piping work was completed. This work added less than 8 hours to the total job completion. The wiring was then completed and the Trane controller activated. The wiring connection to the Hanbell was verified and accepted by the Trane controller and the compressor was brought into service.



Hanbell RC15LF Compressor replacing Trane screw compressor on a Trane RTAA Chiller

